

QUOTATION

Quote No: 0057453

Date: 9/7/2021

Salesperson: MDM

Customer PO#: PICK UP

Bill To: DEREK SCHNEE
256 FAIRWOOD PARKWAY EAST
MORRISVILLE, VT 05661
(802)696-2540

Ship To: DEREK SCHNEE
CUSTOMER PICK UP
MORRISVILLE, VT 05661

Terms: CRED CARD
Cust No: 016064
Contact: DEREK SCHNEE
Phone: 802-696-2540
Email: DEREKSCHNEE@GMAIL.COM

Project Name: NOT PROVIDED
Project Number: PITCH/RAFTER/LFT
16 LF
ROOF TYPE: METAL CORRUGATED
MATERIAL/DIMENSIONS: 27" ON CENTER ASSUMED

Ship Via: CUSTOMER PICK UP
Carrier Acct:

Item	Quantity	UM	Part	Description	Unit Price \$	Discount %	Extension \$
001	8	EA	PP145H204AL	145 2 PP AL 4 FASTEN W/SMPL SL	23.45		187.60
002	32	FT	PP75-AL-08	75 1" OD PIPE-AL (8' LENGTHS, PRICE PER FOOT)	2.46		78.72
004	8	EA	PP56-SS	56 END CAP-SS	1.03		8.24
005	8	EA	PP65-AL	65 END COLLAR-AL	4.29		34.32
SUBTOTAL BEFORE TAX							308.88
TOTAL TAX FOR QUOTE \$							18.53
Total for Quote \$							327.41

ALTERNATE QUOTE 0057452

CUSTOMER PICK UP

PIPE/BAR-STYLE SNOW GUARDS MUST HAVE A BREAK IN THE ASSEMBLY EVERY 100 FEET OF EAVE LENGTH TO ALLOW FOR THERMAL EXPANSION. QUANTITIES SHOULD BE ADJUSTED TO ACCOMMODATE THESE BREAKS.

METAL CORRUGATED/PANEL - THIS PRODUCT MUST BE FASTENED INTO A RIGID STRUCTURAL MEMBER SUCH AS A RAFTER, TRUSS, OR PURLIN.

IT IS THE RESPONSIBILITY OF THE BUYER TO VERIFY THE QUANTITIES QUOTED ARE ACCURATE FOR THE PROJECT PRIOR TO BIDDING.

AS PER DEREK'S LAYOUT. 16 TOTAL LINEAR FEET WITH SNOW GUARDS SPACED 27" ON CENTER ASSUMED

QUANTITIES BASED ON ASSEMBLY LENGTHS AS FOLLOWS: 2 @ 8'

ICE FLAGS ARE OPTIONAL BUT WOULD BE RECOMMENDED FOR THIS PROJECT. YOUR PROJECT WOULD REQUIRE 8 ICE FLAGS AT \$6.12 EACH MINUS YOUR DISCOUNT, PLUS AN INCREASE IN THE POWDER COATING PRICING (IF APPLICABLE). IF YOU WOULD LIKE THEM ADDED TO THIS QUOTE - PLEASE LET US KNOW AND WE WILL REVISE ACCORDINGLY.

ALPINE SNOWGUARDS HAS NOT PROVIDED A LAYOUT FOR THE QUOTE/ORDER. IF YOU CHOOSE NOT TO PROVIDE THE INFORMATION ABOVE AND USE OUR RECOMMENDED LAYOUT THEN THE MINIMUM NUMBER OF PAD STYLE SNOW GUARDS USED SHOULD BE NO LESS THAN 1 PIECE PER 2 SQUARE FEET AND PIPE STYLE SYSTEMS SHOULD BE INSTALLED WITH BRACKETS 18 INCHES ON CENTER WITH A ROW EVERY 5 FEET UP THE ROOF SLOPE UNTIL YOU ARE WITHIN 10 FEET OF THE RIDGE.

Please sign and return this quote to Alpine SnowGuards to confirm 1) that the products, pricing and quantities itemized above are correct, and 2) that you have read, understand and accept Alpine's Terms and Conditions of Sale attached to this quote in a separate document. These terms outline several important issues including our warranty, liability limits and returns policy. This quote is good for 7 days from the quote date. Prices are subject to change without notice thereafter.

Credit Card Number

Exp date

Security Code(CCV)

Date

Page:

Signature:

9/21/21
[Handwritten Signature]